



Permits and Inspections Division  
 1 Centennial Square  
 Victoria, BC V8W 1P6

T 250.361.0344  
 E [permits@victoria.ca](mailto:permits@victoria.ca)  
 www.victoria.ca

# REQUIRED INSPECTIONS

## Building, Plumbing & Electrical

**BUILDING INSPECTIONS - THE OWNER OR HIS OR HER REPRESENTATIVE SHALL GIVE AT LEAST 24 HOURS' NOTICE TO THE CITY WHEN REQUESTING AN INSPECTION AND SHALL OBTAIN AN INSPECTION AND RECEIVE A BUILDING OFFICIAL'S ACCEPTANCE OF THE FOLLOWING ASPECTS OF THE WORK PRIOR TO CONCEALING IT:**

<b>Foundation and Dampproofing</b>	<ul style="list-style-type: none"> <li>Prior to concealing installation of perimeter drain tiles and dampproofing, prior to backfilling.</li> <li>Where required by special condition of the issue permit, BC Land Surveyor Certificate(s) are to be submitted as instructed by special condition.</li> </ul>
<b>Floor Slab</b>	<ul style="list-style-type: none"> <li>The preparation of ground, including ground cover, when required, prior to the placing of a concrete slab.</li> </ul>
<b>Rough-In's</b>	<ul style="list-style-type: none"> <li>Rough-in of factory built chimneys and fireplaces and solid fuel burning appliances.</li> </ul>
<b>Framing</b>	<ul style="list-style-type: none"> <li>Prior to concealing the framing and sheathing.</li> <li>All framing should be complete with plumbing rough-in, electrical rough-in and other mechanical rough-ins requiring notching and drilling complete, as well as firestopping complete.</li> <li>Where required by special condition of the issue permit, BC Land Surveyor Certificate(s) are to be submitted as instructed by special condition.</li> </ul>
<b>Insulation and Vapour Barrier</b>	<ul style="list-style-type: none"> <li>Prior to concealing the insulation and vapour barrier.</li> <li>Where required, a Mid-Construction Verification Report must be submitted (2) two business days prior to inspection.</li> </ul>
<b>Final</b>	<ul style="list-style-type: none"> <li>When the building or structure is substantially complete and ready for occupancy, but before occupancy takes place of the whole or part of the building or structure.</li> <li>Where required, an As-built BC Energy Compliance Report must be submitted (2) two business days prior to inspection.</li> </ul>

**PLUMBING INSPECTIONS - THE OWNER OR HIS OR HER REPRESENTATIVE SHALL GIVE AT LEAST 24 HOURS' NOTICE TO THE CITY WHEN REQUESTING AN INSPECTION AND SHALL OBTAIN AN INSPECTION AND RECEIVE A BUILDING OFFICIAL'S ACCEPTANCE OF THE FOLLOWING ASPECTS OF THE WORK PRIOR TO CONCEALING IT:**

<b>Rough-In</b>	<ul style="list-style-type: none"> <li>Prior to concealing installation of potable water service, sanitary service, storm service.</li> <li>Prior to concealing any underground plumbing that is installed and tested.</li> <li>Plumbing system roughed-in and tested.</li> </ul>
<b>Fire Sprinkler Rough in</b>	<ul style="list-style-type: none"> <li>Prior to concealing sprinkler piping.</li> </ul>
<b>Cap Off</b>	<ul style="list-style-type: none"> <li>Prior to concealing service cap off(s).</li> </ul>
<b>Plumbing Final</b>	<ul style="list-style-type: none"> <li>Plumbing system is installed and tested; bathtubs, showers, site constructed shower pans and plumbing fixtures installed and tested; fixtures installed.</li> </ul>
<b>Fire Sprinkler Final</b>	<ul style="list-style-type: none"> <li>Sprinkler system installed and tested.</li> </ul>

**OVER**



Permits and Inspections Division  
 1 Centennial Square  
 Victoria, BC V8W 1P6

T 250.361.0344  
 E [permits@victoria.ca](mailto:permits@victoria.ca)  
[www.victoria.ca](http://www.victoria.ca)

# REQUIRED INSPECTIONS

Building, Plumbing & Electrical

**ELECTRICAL INSPECTIONS - THE FIELD SAFETY REPRESENTATIVE, OR HOMEOWNER SHALL GIVE AT LEAST 24 HOURS NOTICE TO THE CITY WHEN REQUESTING AN INSPECTION AND RECEIVE A NOTICE OF AN OFFICIAL'S CERTIFICATE OF INSPECTION FOR THE FOLLOWING ASPECTS OF THE WORK PRIOR TO PROCEEDING OR OCCUPANYING:**

<b>Underground</b>	<ul style="list-style-type: none"> <li>• Cable or raceway.</li> <li>• Grounding if not part of a service connection.</li> </ul>
<b>Service Connection</b>	<ul style="list-style-type: none"> <li>• Prior to any utility connection (BC Hydro)</li> <li>• New service and service upgrades.</li> <li>• Damaged services and meter pulls.</li> </ul>
<b>Rough Wire</b>	<ul style="list-style-type: none"> <li>• Pre-drywall.</li> <li>• Pre-concealment of any electrical installation.</li> </ul>
<b>Safety Survey</b>	<ul style="list-style-type: none"> <li>• Field Safety Representative acknowledges that all electrical hazards, if any are made safe.</li> </ul>
<b>Work in Progress</b>	<ul style="list-style-type: none"> <li>• No inspection within 180 days of the last inspection.</li> <li>• Permit extension.</li> </ul>
<b>Occupancy</b>	<ul style="list-style-type: none"> <li>• All life safety systems are complete.</li> <li>• All wiring is safe and compliant.</li> <li>• Safe to occupy.</li> </ul>
<b>Final</b>	<ul style="list-style-type: none"> <li>• All electrical work is 100% complete.</li> </ul>